Coastal Construction Manual

Principles and Practices of Planning, Siting, Designing, Constructing, and Maintaining Residential Buildings in Coastal Areas (Fourth Edition)

FEMA P-55 / Volume II / August 2011

FEMA

Coastal Construction Manual

Principles and Practices of Planning, Siting, Designing, Constructing, and Maintaining Residential Buildings in Coastal Areas (Fourth Edition)

FEMA P-55 / Volume II / August 2011

FEMA

Preface

The 2011 *Coastal Construction Manual*, Fourth Edition (FEMA P-55), is a two-volume publication that provides a comprehensive approach to planning, siting, designing, constructing, and maintaining homes in the coastal environment. Volume I of the *Coastal Construction Manual* provides information about hazard identification, siting decisions, regulatory requirements, economic implications, and risk management. The primary audience for Volume I is design professionals, officials, and those involved in the decision-making process.

Volume II contains in-depth descriptions of design, construction, and maintenance practices that, when followed, will increase the durability of residential buildings in the harsh coastal environment and reduce economic losses associated with coastal natural disasters**.** The primary audience for Volume II is the design professional who is familiar with building codes and standards and has a basic understanding of engineering principles.

Volume II is not a standalone reference for designing homes in the coastal environment. The designer should have access to and be familiar with the building codes and standards that are discussed in Volume II and listed in the reference section at the end of each chapter. The designer should also have access to the building codes and standards that have been adopted by the local jurisdiction if they differ from the standards and codes that are cited in Volume II. If the local jurisdiction having authority has not adopted a building code, the most recent code should be used. Engineering judgment is sometimes necessary, but designers should not make decisions that will result in a design that does not meet locally adopted building codes.

The topics that are covered in Volume II are as follows:

- **Chapter 7 –** Introduction to the design process, minimum design requirements, losses from natural hazards in coastal areas, cost and insurance implications of design and construction decisions, sustainable design, and inspections.

- **Chapter 8 –** Site-specific loads, including from snow, flooding, tsunamis, high winds, tornadoes, seismic events, and combinations of loads. Example problems are provided to illustrate the application of design load provisions of ASCE 7-10, *Minimum Design Loads for Buildings and Other Structures*.
- **Chapter 9 –** Load paths, structural connections, structural failure modes, breakaway walls, building materials, and appurtenances.
- **Chapter 10 –** Foundations, including design criteria, requirements and recommendations, style selection (e.g., open, closed), pile capacity in soil, and installation.
- **Chapter 11 –** Building envelope, including floors in elevated buildings, exterior doors, windows and skylights, non-loading-bearing walls, exterior wall coverings, soffits, roof systems, and attic vents.
- **Chapter 12 –** Installing mechanical equipment and utilities.
- **Chapter 13 –** Construction, including the foundation, structural frame, and building envelope. Common construction mistakes, material selection and durability, and techniques for improving resistance to decay and corrosion are also discussed.
- **Chapter 14 –** Maintenance of new and existing buildings, including preventing damage from corrosion, moisture, weathering, and termites; building elements that require frequent maintenance; and hazard-specific maintenance techniques.
- **Chapter 15 –** Evaluating existing buildings for the need for and feasibility of retrofitting for wildfire, seismic, flood, and wind hazards and implementing the retrofitting. Wind retrofit packages that can be implemented during routine maintenance are also discussed (e.g., replacing roof shingles).

For additional information on residential coastal construction, see the FEMA Residential Coastal Construction Web site at http://www.fema.gov/rebuild/mat/fema55.shtm.

Acknowledgments

Fourth Edition Authors and Key Contributors

William Coulbourne, Applied Technology Council
Christopher P. Jones, Durham, NC
Omar Kapur, URS Group, Inc.
Vasso Koumoudis, URS Group, Inc.
Philip Line, URS Group, Inc.
David K. Low, DK Low and Associates
Glenn Overcash, URS Group, Inc.
Samantha Passman, URS Group, Inc.
Adam Reeder, Atkins
Laura Seitz, URS Group, Inc.
Thomas Smith, TLSmith Consulting
Scott Tezak, URS Group, Inc. – Consultant Project Manager

Fourth Edition Volume II Reviewers and Contributors

Katy Goolsby-Brown, FEMA Region IV
John Ingargiola, FEMA Headquarters – Technical Assistance and Research Contracts Program Manager
John Plisich, FEMA Region IV
Paul Tertell, FEMA Headquarters – Project Manager
Ronald Wanhanen, FEMA Region VI
Gregory P. Wilson, FEMA Headquarters
Brad Douglas, American Forest and Paper Association
Gary Ehrlich, National Association of Home Builders
Dennis Graber, National Concrete Masonry Association
David Kriebel, United States Naval Academy
Marc Levitan, National Institute of Standards and Technology
Tim Mays, The Military College of South Carolina
Sam Nelson, Texas Department of Insurance
Janice Olshesky, Olshesky Design Group, LLC
Michael Powell, Delaware Department of Natural Resources and Environmental Control
David Prevatt, University of Florida
Timothy Reinhold, Insurance Institute for Business & Home Safety
Tom Reynolds, URS Group, Inc.
Michael Rimoldi, Federal Alliance for Safe Homes
Randy Shackelford, Simpson Strong-Tie
John Squerciati, Dewberry
Keqi Zhang, Florida International University

Fourth Edition Technical Editing, Layout, and Illustration

Diana Burke, URS Group, Inc.
Lee-Ann Lyons, URS Group, Inc.
Susan Ide Patton, URS Group, Inc.
Billy Ruppert, URS Group, Inc.

Contents

Chapter 7. Pre-Design Considerations 7-1

7.1 Design Process 7-2

7.2 Design Requirements 7-3

7.3 Determining the Natural Hazard Risk 7-3

7.4 Losses Due to Natural Hazards in Coastal Areas 7-5

7.5 Initial, Long-Term, and Operational Costs 7-6

7.5.1 Cost Implications of Siting Decisions 7-7

7.5.2 Cost Implications of Design Decisions 7-7

7.5.3 Benefits and Cost Implications of Siting, Design, and Construction Decisions 7-11

7.6 Hazard Insurance 7-12

7.6.1 Flood Insurance 7-13

7.6.1.1 Rating Factors 7-13

7.6.1.2 Coverage 7-17

7.6.1.3 Premiums 7-18

7.6.1.4 Designing to Achieve Lower Flood Insurance Premiums 7-20

7.6.2 Wind Insurance 7-21

7.6.2.1 Territory 7-22

7.6.2.2 Fire Protection Class 7-22

7.6.2.3 Building Code Effectiveness Grading Schedule 7-22

7.6.2.4 Construction Type 7-23

7.6.2.5 Protective Devices 7-23

7.6.3 Earthquake Insurance 7-24

7.7 Sustainable Design Considerations 7-24

7.8 Inspection Considerations 7-25

7.9 References 7-26

Chapter 8. Determining Site-Specific Loads 8-1

8.1 Dead Loads 8-3

8.2 Live Loads 8-3

8.3 Concept of Tributary or Effective Area and Application of Loads to a Building 8-4

8.4 Snow Loads 8-5

8.5 Flood Loads 8-5

8.5.1 Design Flood 8-5

8.5.2 Design Flood Elevation 8-6

8.5.3 Design Stillwater Flood Depth 8-9

8.5.5 Design Breaking Wave Height 8-15

8.5.6 Design Flood Velocity 8-15

8.5.7 Hydrostatic Loads 8-17

8.5.8 Wave Loads 8-20

8.5.8.1 Breaking Wave Loads on Vertical Piles 8-21

8.5.8.2 Breaking Wave Loads on Vertical Walls 8-22

8.5.8.3 Wave Slam 8-25

8.5.9 Hydrodynamic Loads 8-28

8.5.10 Debris Impact Loads 8-31

8.5.11 Localized Scour 8-34

8.5.12 Flood Load Combinations 8-37

8.6 Tsunami Loads 8-47

8.7 Wind Loads 8-47

8.7.1 Determining Wind Loads 8-49

8.7.2 Main Wind Force Resisting System 8-52

8.7.3 Components and Cladding 8-61

8.8 Tornado Loads 8-67

8.9 Seismic Loads 8-68

8.10 Load Combinations 8-73

8.11 References 8-81

Chapter 9. Designing the Building 9-1

9.1 Continuous Load Path 9-1
9.1.1 Roof Sheathing to Framing Connection (Link #1) 9-4
9.1.2 Roof Framing to Exterior Wall (Link #2) 9-8
9.1.3 Wall Top Plate to Wall Studs (Link #3) 9-10
9.1.4 Wall Sheathing to Window Header (Link #4) 9-12
9.1.5 Window Header to Exterior Wall (Link #5) 9-12
9.1.6 Wall to Floor Framing (Link #6) 9-15
9.1.7 Floor Framing to Support Beam (Link #7) 9-17
9.1.8 Floor Support Beam to Foundation (Pile) (Link #8) 9-18

9.2 Other Load Path Considerations 9-21
9.2.1 Uplift Due to Shear Wall Overturning 9-21
9.2.2 Gable Wall Support 9-24
9.2.3 Connection Choices 9-24
9.2.4 Building Eccentricities 9-27
9.2.5 Framing System 9-27
9.2.5.1 Platform Framing 9-27
9.2.5.2 Concrete/Masonry 9-27
9.2.5.3 Moment-Resisting Frames 9-28
9.2.6 Roof Shape 9-30

9.3 Breakaway Wall Enclosures 9-30

9.4 Building Materials 9-33
9.4.1 Materials Below the DFE 9-34
9.4.2 Materials Above the DFE 9-35
9.4.3 Material Combinations 9-35
9.4.4 Fire Safety Considerations 9-36
9.4.5 Corrosion 9-37

9.5 Appurtenances 9-38
9.5.1 Decks and Covered Porches Attached to Buildings 9-38
9.5.1.1 Handrails 9-39
9.5.1.2 Stairways 9-39
9.5.2 Access to Elevated Buildings 9-39
9.5.3 Pools and Hot Tubs 9-40

9.6 References 9-43

Chapter 10. Designing the Foundation 10-1

10.1 Foundation Design Criteria 10-2

10.2 Foundation Styles 10-2
10.2.1 Open Foundations 10-3
10.2.2 Closed Foundations 10-3
10.2.3 Deep Foundations 10-4
10.2.4 Shallow Foundations 10-4

10.3 Foundation Design Requirements and Recommendations 10-4
10.3.1 Foundation Style Selection 10-5
10.3.2 Site Considerations 10-5
10.3.3 Soils Data 10-5
10.3.3.1 Sources of Published Soils Data 10-6
10.3.3.2 Soils Data from Site Investigations 10-6

10.4 Design Process 10-10

10.5 Pile Foundations 10-11
10.5.1 Compression Capacity of Piles – Resistance to Gravity Loads 10-12
10.5.2 Tension Capacity of Piles 10-15
10.5.3 Lateral Capacity of Piles 10-18
10.5.4 Pile Installation 10-20
10.5.5 Scour and Erosion Effects on Pile Foundations 10-21
10.5.6 Grade Beams for Pile Foundations 10-23

10.6 Open/Deep Foundations 10-25
10.6.1 Treated Timber Pile Foundations 10-25
10.6.1.1 Wood Pile-to-Beam Connections 10-26
10.6.1.2 Pile Bracing 10-27
10.6.1.3 Timber Pile Treatment 10-31
10.6.2 Other Open/Deep Pile Foundation Styles 10-31

10.7 Open/Shallow Foundations 10-34

10.8 Closed/Shallow Foundations 10-35

10.9 Pier Foundations 10-36
10.9.1 Pier Foundation Design Examples 10-37
10.9.2 Pier Foundation Summary 10-45

10.10 References 10-46

Chapter 11. Designing the Building Envelope 11-1

11.1 Floors in Elevated Buildings 11-4

11.2 Exterior Doors 11-4
11.2.1 High Winds 11-6
11.2.1.1 Loads and Resistance 11-6
11.2.1.2 Wind-Borne Debris 11-7
11.2.1.3 Durability 11-7
11.2.1.4 Water Infiltration 11-7

11.3 Windows and Sklylights 11-9
11.3.1 High Winds 11-9
11.3.1.1 Loads and Resistance 11-9
11.3.1.2 Wind-Borne Debris 11-10
11.3.1.3 Durability 11-13
11.3.1.4 Water Infiltration 11-14
11.3.2 Seismic 11-15
11.3.3 Hail 11-15

11.4 Non-Load-Bearing Walls, Wall Coverings, and Soffits 11-15
11.4.1 High Winds 11-16
11.4.1.1 Exterior Walls 11-16
11.4.1.2 Flashings 11-21
11.4.1.3 Soffits 11-22
11.4.1.4 Durability 11-23
11.4.2 Seismic 11-24

11.5 Roof Systems 11-24
11.5.1 Asphalt Shingles 11-25
11.5.1.1 High Winds 11-25
11.5.1.2 Hail 11-36
11.5.2 Fiber-Cement Shingles 11-36
11.5.2.1 High Winds 11-37
11.5.2.2 Seismic 11-37
11.5.2.3 Hail 11-37
11.5.3 Liquid-Applied Membranes 11-37
11.5.3.1 High Winds 11-37
11.5.3.2 Hail 11-38
11.5.4 Tiles 11-38

11.5.4.1 High Winds 11-38
11.5.4.2 Seismic 11-43
11.5.4.3 Hail 11-45
11.5.5 Metal Panels and Metal Shingles 11-45
11.5.5.1 High Winds 11-45
11.5.5.2 Hail 11-46
11.5.6 Slate 11-46
11.5.6.1 High Winds 11-46
11.5.6.2 Seismic 11-47
11.5.6.3 Hail 11-47
11.5.7 Wood Shingles and Shakes 11-47
11.5.7.1 High Winds 11-47
11.5.7.2 Hail 11-48
11.5.8 Low-Slope Roof Systems 11-48
11.5.8.1 High Winds 11-49
11.5.8.2 Seismic 11-49
11.5.8.3 Hail 11-49

11.6 Attic Vents 11-49

11.7 Additional Environmental Considerations 11-52
11.7.1 Sun 11-52
11.7.2 Wind-Driven Rain 11-52

11.8 References 11-52
List of Figures 11-58
List of Tables 11-60

Chapter 12. Installing Mechanical Equipment and Utilities 12-1

12.1 Elevators 12-1

12.2 Exterior-Mounted Mechanical Equipment 12-2
12.2.1 High Winds 12-2
12.2.2 Flooding 12-3
12.2.3 Seismic Events 12-6

12.3 Interior Mechanical Equipment 12-6

12.4 Electric Utility, Telephone, and Cable TV Systems 12-6
12.4.1 Emergency Power 12-9

12.5 Water and Wastewater Systems 12-10
12.5.1 Wells 12-10
12.5.2 Septic Systems 12-11
12.5.3 Sanitary Systems 12-11
12.5.4 Municipal Water Connections 12-12
12.5.5 Fire Sprinkler Systems 12-12

12.6 References 12-12

Chapter 13. Constructing the Building 13-1

13.1 Foundation Construction 13-2
13.1.1 Layout 13-2
13.1.2 Pile Foundations 13-5
13.1.3 Masonry Foundation Construction 13-8
13.1.4 Concrete Foundation Construction 13-10
13.1.5 Wood Foundation Construction 13-12
13.1.6 Foundation Material Durability 13-13
13.1.7 Field Preservative Treatment 13-17
13.1.8 Substitutions 13-18
13.1.9 Foundation Inspection Points 13-18
13.1.10 Top Foundation Issues for Builders 13-18

13.2 Structural Frame 13-19
13.2.1 Structural Connections 13-19
13.2.2 Floor Framing 13-23
13.2.2.1 Horizontal Beams and Girders 13-24
13.2.2.2 Substitution of Floor Framing Materials 13-25
13.2.2.3 Floor Framing Inspection Points 13-25
13.2.3 Wall Framing 13-25
13.2.3.1 Substitution of Wall Framing Materials 13-27
13.2.3.2 Wall Framing Inspection Points 13-27
13.2.4 Roof Framing 13-27
13.2.4.1 Substitution of Roof Framing Materials 13-28
13.2.4.2 Roof Frame Inspection Points 13-28
13.2.5 Top Structural Frame Issues for Builders 13-28

13.3 Building Envelope 13-29
13.3.1 Substitution of Building Envelope Materials 13-30

13.3.2 Building Envelope Inspection Points 13-31
13.3.3 Top Building Envelope Issues for Builders 13-31
13.4 References 13-32

Chapter 14. Maintaining the Building 14-1
14.1 Effects of Coastal Environment 14-2
14.1.1 Corrosion 14-2
14.1.2 Moisture 14-3
14.1.3 Weathering 14-4
14.1.4 Termites 14-4
14.2 Building Elements That Require Frequent Maintenance 14-5
14.2.1 Glazing 14-7
14.2.2 Siding 14-7
14.2.3 Roofs 14-8
14.2.4 Exterior-Mounted Mechanical and Electrical Equipment 14-9
14.2.5 Decks and Exterior Wood 14-9
14.2.6 Metal Connectors 14-10
14.3 Hazard-Specific Maintenance Techniques 14-11
14.3.1 Flooding 14-12
14.3.2 Seismic and Wind 14-12
14.4 References 14-13

Chapter 15. Retrofitting Buildings for Natural Hazards 15-1
15.1 Wildfire Mitigation 15-2
15.2 Seismic Mitigation 15-5
15.3 Flood Mitigation 15-8
15.3.1 Elevation 15-8
15.3.2 Relocation 15-10
15.3.3 Dry Floodproofing 15-11
15.3.4 Wet Floodproofing 15-12
15.3.5 Floodwalls and Levees 15-13
15.3.6 Multihazard Mitigation 15-14
15.4 High-Wind Mitigation 15-15

15.4.1 Evaluating Existing Homes 15-16
15.4.2 Wind Retrofit Mitigation Packages 15-16
15.4.2.1 Basic Mitigation Package 15-17
15.4.2.2 Intermediate Mitigation Package 15-19
15.4.2.3 Advanced Mitigation Package 15-19
15.4.2.4 Additional Mitigation Measures 15-19
15.4.3 FEMA Wind Retrofit Grant Programs 15-19
15.5 References 15-21

Acronyms A-1

Glossary G-1

Index I-1

List of Figures

Chapter 7

Figure 7-1. Design framework for a successful building, incorporating cost, risk tolerance, use, location, materials, and hazard resistance 7-3

Figure 7-2. Average damage per structure vs. distance from the Florida Coastal Construction Control Line for Bay County, FL 7-4

Figure 7-3. Basic benefit-cost model 7-12

Chapter 8

Figure 8-1. Summary of typical loads and characteristics affecting determination of design load 8-2

Figure 8-2. Examples of tributary areas for different structural elements 8-4

Figure 8-3. Flowchart for estimating maximum likely design stillwater flood depth at the site 8-7

Figure 8-4. Erosion's effects on ground elevation 8-8

Figure 8-5. Parameters that are determined or affected by flood depth 8-9

Figure 8-6. Velocity versus design stillwater flood depth 8-17

Figure 8-7. Lateral flood force on a vertical component 8-19

Figure 8-8. Vertical (buoyant) flood force 8-20
Figure 8-9. Breaking wave pressure distribution against a vertical wall 8-23
Figure 8-10. Wave crests not parallel to wall 8-24
Figure 8-11. Water depth versus wave height, and water depth versus breaking wave force against, a vertical wall 8-25
Figure 8-12. Lateral wave slam against an elevated building 8-26
Figure 8-13. Hydrodynamic loads on a building 8-28
Figure 8-14. Scour at single vertical foundation member, with and without underlying scour resistant stratum 8-34
Figure 8-15. Deep scour around foundation piles, Hurricane Ike 8-35
Figure 8-16. Scour around a group of foundation piles 8-36
Figure 8-17. Effect of wind on an enclosed building and a building with an opening 8-48
Figure 8-18. Distribution of roof, wall, and internal pressures on one-story, pile-supported building 8-49
Figure 8-19. Variation of maximum negative MWFRS pressures based on envelope procedures for low-rise buildings 8-51
Figure 8-20. Components and cladding wind pressures 8-62
Figure 8-21. Effect of seismic forces on supporting piles 8-69

Chapter 9

Figure 9-1. Load path failure at gable end 9-2
Figure 9-2. Load path failure in connection between home and its foundation 9-2
Figure 9-3. Roof framing damage and loss due to load path failure at top of wall/roof structure connection 9-3
Figure 9-4. Load path failure in connections between roof decking and roof framing 9-3
Figure 9-5. Newer home damaged from internal pressurization and inadequate connections 9-4
Figure 9-6. Example load path for case study building 9-5
Figure 9-7. Connection of the roof sheathing to the roof framing (Link #1) 9-6
Figure 9-8. Connection of roof framing to exterior wall (Link #2) 9-8
Figure 9-9. Connection of truss to wood-frame wall 9-10

Figure 9-10. Roof truss-to-masonry wall connectors embedded into concrete-filled or grouted masonry cell 9-11
Figure 9-11. Connection of wall top plate-to-wall stud (Link #3) 9-11
Figure 9-12. Wall top plate-to-wall stud metal connector 9-12
Figure 9-13. Connection of wall sheathing to window header (Link #4) 9-13
Figure 9-14. Connection of window header to exterior wall (Link #5) 9-13
Figure 9-15. Connection of wall to floor framing (Link #6) 9-15
Figure 9-16. Connection of floor framing to support beam (Link #7) 9-17
Figure 9-17. Metal joist-to-beam connector 9-17
Figure 9-18. Connection of floor support beam to foundation (Link #8) 9-19
Figure 9-19. Diaphragm stiffening and corner pile bracing to reduce pile cap rotation 9-20
Figure 9-20. Shear wall holddown connector with bracket attached to a wood beam 9-24
Figure 9-21. Gable-end failure 9-25
Figure 9-22. Gable-end bracing detail; nailing schedule, strap specification, brace spacing, and overhang limits should be adapted for the applicable basic wind speed 9-26
Figure 9-23. Example of two-story platform framing on a pile-and-beam foundation 9-28
Figure 9-24. Two-story masonry wall with wood floor and roof framing 9-29
Figure 9-25. Steel moment frame with large opening 9-29
Figure 9-26. Gable-end failure caused by high winds 9-31
Figure 9-27. Hip roof that survived high winds with little to no damage 9-31
Figure 9-28. Typical failure mode of breakaway wall beneath an elevated building 9-32
Figure 9-29. Breakaway wall panel prevented from breaking away cleanly by utility penetrations 9-32
Figure 9-30. Lattice beneath an elevated house in Zone V 9-33
Figure 9-31. House being constructed with a steel frame on wood piles 9-36
Figure 9-32. Townhouse framing system 9-37
Figure 9-33. Recommendations for orientation of in-ground pools 9-41
Figure 9-34. Recommended contraction joint layout for frangible slab-on-grade below elevated building 9-42

Chapter 10

Figure 10-1. Closed foundation failure due to erosion and scour undermining..... 10-4
Figure 10-2. Near collapse due to insufficient pile embedment.....10-13
Figure 10-3. Surviving pile foundation.....10-13
Figure 10-4. Deflected pile shape for an unbraced pile 10-19
Figure 10-5. Pier installation methods..... 10-20
Figure 10-6. Scour and erosion effects on piling embedment.....10-21
Figure 10-7. Column connection failure 10-24
Figure 10-8. Scour around grade beam.....10-25
Figure 10-9. Profile of timber pile foundation type..... 10-26
Figure 10-10. Diagonal bracing using dimensional lumber 10-28
Figure 10-11. Diagonal bracing schematic..... 10-28
Figure 10-12. Knee bracing..... 10-30
Figure 10-13. Section view of a steel pipe pile with concrete column and grade beam foundation type.....10-32
Figure 10-14. Section view of a foundation constructed with reinforced concrete beams and columns to create portal frames.....10-33
Figure 10-15. Profile of an open/shallow foundation 10-34
Figure 10-16. Stem wall foundation design 10-36
Figure 10-17. Performance comparison of pier foundations..... 10-37
Figure 10-18. Pier foundation and spread footing under gravity loading 10-38
Figure 10-19. Pier foundation and spread footing exposed to uplift forces..... 10-38
Figure 10-20. Pier foundation and spread footing exposed to uplift and lateral forces 10-39

Chapter 11

Figure 11-1. Good structural system performance but the loss of shingles, underlayment, siding, housewrap, and soffts resulted in significant interior water damage.....11-2
Figure 11-2. Numerous wind-borne debris scars and several missing asphalt shingles.....11-3

Figure 11-3. House that survived a wildfire due in part to fire-resistant walls and roof while surrounding houses were destroyed 11-3

Figure 11-4. Plywood panels on the underside of a house that blew away because of excessive nail spacing 11-5

Figure 11-5. Sliding glass doors pulled out of their tracks by wind suction 11-5

Figure 11-6. Garage door blown from its track as a result of positive pressure 11-6

Figure 11-7. A 3/8-inch gap between the threshold and door which allowed wind-driven rain to enter the house 11-8

Figure 11-8. Window frame pulled out of the wall because of inadequate window frame attachment 11-9

Figure 11-9. Very old building with robust shutters constructed of 2x4 lumber, bolted connections, and heavy metal hinges 11-10

Figure 11-10. Unprotected cupola window that was broken 11-11

Figure 11-11. Design pressure and impact-resistance information in a permanent window label 11-12

Figure 11-12. Roll-up shutter slats that detached from the tracks 11-12

Figure 11-13. Shutter punctured by roof tile 11-13

Figure 11-14. House in Puerto Rico with metal jalousie louvers 11-14

Figure 11-15. Blown-off vinyl siding and foam sheathing; some blow-off of interior gypsum board 11-17

Figure 11-16. Blown-off fiber cement siding; broken window 11-18

Figure 11-17. Four brick veneer failure modes; five corrugated ties that were not embedded in the mortar joints 11-18

Figure 11-18. Typical EIFS assemblies 11-19

Figure 11-19. Blown-off EIFS, resulting in extensive interior water damage; detachment of the gypsum board or stud blow off; two windows broken by debris 11-20

Figure 11-20. Collapse of the breakaway wall, resulting in EIFS peeling 11-21

Figure 11-21. EIFS with a barrier design: blown-off roof decking; severely rotted OSB due to leakage at windows 11-22

Figure 11-22. Blown-away soffit, which allowed wind-driven rain to enter the attic 11-23

Figure 11-23. Blow-off of several newer shingles on a roof that had been re-covered by installing new asphalt shingles on top of old shingles 11-25

Figure 11-24. Small area of sheathing that was exposed after loss of a few shingles and some underlayment 11-26

Figure 11-25. Typical underlayment attachment 11-26

Figure 11-26. Enhanced underlayment Option 1, first variation: self-adhering modified bitumen over the sheathing 11-27

Figure 11-27. Enhanced underlayment Option 1, second variation: self-adhering modified bitumen over the felt 11-28

Figure 11-28. House that used enhanced underlayment Option 3 with taped sheathing joints. The self-adhering modified bitumen tape was stapled because of bonding problems 11-29

Figure 11-29. Underlayment that was not lapped over the hip 11-30

Figure 11-30. Loss of shingles and underlayment along the eave and loss of a few hip shingles 11-31

Figure 11-31. Loss of shingles and underlayment along the rake 11-31

Figure 11-32. Incorrect installation of the starter course 11-32

Figure 11-33. Uplift loads along the rake that are transferred to the ends of the rows of self-sealing adhesive 11-33

Figure 11-34. A bleeder strip that was used at a rake blow-off 11-34

Figure 11-35. Inadequate sealing of the self-sealing adhesive at a hip 11-34

Figure 11-36. Proper and improper location of shingle fasteners (nails) 11-35

Figure 11-37. Proper and improper location of laminated shingle fasteners (nails) 11-35

Figure 11-38. Shingles that unzipped at the band lines 11-36

Figure 11-39. Blow-off of eave and hip tiles and some broken tiles in the field of the roof 11-39

Figure 11-40. Large area of blown-off underlayment on a mortar-set tile roof 11-39

Figure 11-41. Blow-off of wire-tied tiles installed over a concrete deck 11-39

Figure 11-42. Extensive blow-off of mortar-set tiles 11-40

Figure 11-43. Blown-offadhesive-set tile 11-40

Figure 11-44. Adhesive that debonded from the cap sheet 11-41

Figure 11-45. Blow-off of mechanically attached tiles 11-41

Figure 11-46. Blow-off of hip tiles that were nailed to a ridge board and set in mortar 11-42

Figure 11-47. Damage to field tiles caused by tiles from another area of the roof, including a hip tile....11-42

Figure 11-48. The fastener heads on this mechanically attached tile roof had corroded....11-43

Figure 11-49. Area of the roof where tiles were not nailed to batten strips....11-44

Figure 11-50. Tiles that were nailed to thin wood sheathing....11-44

Figure 11-51. Tile that slipped out from under the hip tiles....11-45

Figure 11-52. Blow-off of one of the nailers caused panels to progressively fail; cantilevered condenser platform; broken window....11-46

Figure 11-53. Damaged slate roof with nails that typically pulled out of the deck....11-47

Figure 11-54. Loss of wood shingles due to fastener corrosion....11-48

Figure 11-55. Method for maintaining a continuous load path at the roof ridge by nailing roof sheathing....11-50

Figure 11-56. Holes drilled in roof sheathing for ventilation and roof diaphragm action is maintained....11-51

Chapter 12

Figure 12-1. Condenser damaged as a result of insufficient elevation, Hurricane Georges (U.S. Gulf Coast, 1998)....12-4

Figure 12-2. Proper elevation of an air-conditioning condenser in a floodprone area; additional anchorage is recommended....12-4

Figure 12-3. Small piles supporting a platform broken by floodborne debris....12-5

Figure 12-4. Electric service meters and feeders that were destroyed by floodwaters during Hurricane Opal (1995)....12-7

Figure 12-5. Recommended installation techniques for electric and plumbing lines and utility elements....12-8

Figure 12-6. Damage caused by dropped overhead service, Hurricane Marilyn (U.S. Virgin Islands, 1995)....12-9

Chapter 13

Figure 13-1. Site layout....13-3

Figure 13-2. Typical pile notching process....13-4

Figure 13-3. Improper overnotched wood pile....13-4

Figure 13-4. Properly notched pile 13-5
Figure 13-5. Typical wood pile foundation 13-6
Figure 13-6. Open masonry foundation 13-10
Figure 13-7. Concrete foundation 13-11
Figure 13-8. Concrete house 13-11
Figure 13-9. Wood decay at the base of a post supported by concrete 13-14
Figure 13-10. Examples of minimizing the least dimension of wood contact surfaces 13-15
Figure 13-11. Drip cut to minimize horizontal water movement along the bottom surface of a wood member 13-15
Figure 13-12. Exposure of end grain in stair stringer cuts 13-16
Figure 13-13. Deterioration in a notched stair stringer 13-16
Figure 13-14. Alternative method of installing stair treads 13-17
Figure 13-15. Connector failure caused by insufficient nailing 13-20
Figure 13-16. Reinforcement of overnotched piles 13-21
Figure 13-17. Beam support at misaligned piles 13-22
Figure 13-18. Proper pile notching for two-member and four-member beams 13-22
Figure 13-19. Proper use of metal twist strap ties; solid blocking between floor joists 13-23
Figure 13-20. Engineered joists used as floor joists with proper metal brace to keep the bottoms of the joists from twisting; engineered wood beam 13-24
Figure 13-21. Acceptable locations for splices in multiple-member girders 13-25
Figure 13-22. Full-height sheathing to improve transfer of shear 13-26

Chapter 14

Figure 14-1. Pile that appears acceptable from the exterior but has interior decay 14-1
Figure 14-2. Wood decay behind a metal beam connector 14-3
Figure 14-3. Severely corroded deck connectors 14-11
Figure 14-4. Deteriorated wood sill plate 14-12

Chapter 15

Figure 15-1. The three concentric zones of defensible space 15-2
Figure 15-2. The building envelope 15-3
Figure 15-3. Fire spreads vertically through vegetation 15-3
Figure 15-4. FEMA P-737, *Home Builder's Guide to Construction in Wildlife Zones: Technical Fact Sheet Series* 15-4
Figure 15-5. FEMA 232, *Homebuilders Guide to Earthquake Resistant Design and Construction* 15-5
Figure 15-6. A house with severe damage due to cripple wall failure 15-6
Figure 15-7. Common open-front configurations in one- and two- family detached houses 15-7
Figure 15-8. FEMA 530, *Earthquake Safety Guide for Homeowners* 15-8
Figure 15-9. Home elevated on piles 15-9
Figure 15-10. Preparing a building for relocation 15-10
Figure 15-11. Dry floodproofed structure 15-11
Figure 15-12. Wet floodproofed structure 15-13
Figure 15-13. Home protected by a floodwall and a levee 15-15
Figure 15-14. FEMA P-804, *Wind Retrofit Guide for Residential Buildings* 15-15
Figure 15-15. Wind Retrofit Mitigation Packages 15-17
Figure 15-16. Bracing gable end overhangs 15-18
Figure 15-17. Sprayed polyurethane foam adhesive to secure roof deck panels 15-18
Figure 15-18. Continuous load path for wind-uplift of a residential, wood-frame building 15-20
Figure 15-19. HMA grant process 15-21

List of Tables

Chapter 7

Table 7-1. Examples of Flood and Wind Mitigation Measures 7-8
Table 7-2. Sample NFIP Flood Insurance Premiums for Buildings in Zone A 7-19

Table 7-3. Sample NFIP Flood Insurance Premiums for Buildings in Zone V Free of Obstruction Below the Lowest Floor 7-19

Table 7-4. Sample NFIP Flood Insurance Premiums for Buildings in Zone V with Obstruction Below the Lowest Floor 7-20

Chapter 8

Table 8-1. Value of Dynamic Pressure Coefficient (*Cp*) as a Function of Probability of Exceedance 8-23

Table 8-2. Drag Coefficients for Ratios of Width to Depth (w/d_s) and Width to Height (w/h) 8-29

Table 8-3. Depth Coefficient (C_D) by Flood Hazard Zone and Water Depth 8-33

Table 8-4. Values of Blockage Coefficient C_B 8-33

Table 8-5. Selection of Flood Loads for F_a in ASCE 7-10 Load Combinations for Global Forces 8-37

Table 8-6. Roof Uplift Connector Loads at Building Edge Zones 8-53

Table 8-7. Lateral Diaphragm Load from Wind Perpendicular to Ridge 8-53

Table 8-8. Roof and Wall Sheathing Suction Loads 8-63

Table 8-9. Lateral Connector Loads from Wind at Building End Zones 8-63

Chapter 9

Table 9-1. General Guidance for Selection of Materials 9-33

Chapter 10

Table 10-1. Foundation Styles in Coastal Areas 10-3

Table 10-2. ASTM D2487 10-Soil Classifications 10-8

Table 10-3. Advantages and Special Considerations of Three Types of Pile Materials 10-12

Table 10-4. Bearing Capacity Factors (*Nq*) 10-14

Table 10-5. Earth Pressure Coefficients 10-14

Table 10-6. Friction Angle Between Soil and Pile (δ) 10-15

Table 10-7. Allowable Compression and Tension of Wood Piles Based on Varying Diameters, Embedments, and Installation Methods 10-18

Table 10-8. Values of n_h Modulus of Subgrade Reaction 10-19

Table 10-9. Advantages and Special Considerations of Pile Installation Methods....10-21
Table 10-10. Example Analysis of the Effects of Scour and Erosion on a Foundation.... 10-23

Chapter 11

Table 11-1. Allowable Basic Wind Speed as a Function of Class 11-31

Chapter 13

Table 13-1. Foundation and Floor Framing Inspection Points 13-18
Table 13-2. Wall Inspection Points 13-27
Table 13-3. Roof Frame Inspection Points 13-29
Table 13-4. Building Envelope Inspection Points 13-31

Chapter 14

Table 14-1. Maintenance Inspection Checklist 14-5

Chapter 15

Table 15-1. Advantages and Disadvantages of Elevation 15-9
Table 15-2. Advantages and Disadvantages of Relocation 15-10
Table 15-3. Advantages and Disadvantages of Dry Floodproofing 15-12
Table 15-4. Advantages and Disadvantages of Wet Floodproofing 15-13
Table 15-5. Advantages and Disadvantages of a Floodwall or Levee.... 15-14

List of Equations

Chapter 8

Equation 8.1. Design Stillwater Flood Depth....8-10
Equation 8.2. Design Flood Velocity....8-16
Equation 8.3. Lateral Hydrostatic Load....8-18
Equation 8.4. Vertical (Buoyant) Hydrostatic Force 8-19
Equation 8.5. Breaking Wave Load on Vertical Piles 8-21

Equation 8.6. Breaking Wave Load on Vertical Walls 8-22
Equation 8.7. Lateral Wave Slam 8-26
Equation 8.8. Hydrodynamic Load (for All Flow Velocities) 8-29
Equation 8.9. Debris Impact Load 8-32
Equation 8.10. Localized Scour Around a Single Vertical Pile 8-35
Equation 8.11. Total Localized Scour Around Vertical Piles 8-36
Equation 8.12. Total Scour Depth Around Vertical Walls and Enclosures 8-37
Equation 8.13. Velocity Pressure 8-50
Equation 8.14. Design Wind Pressure for Low-Rise Buildings 8-50
Equation 8.15. Seismic Base Shear by Equivalent Lateral Force Procedure 8-69
Equation 8.16. Vertical Distribution of Seismic Forces 8-70

Chapter 10

Equation 10.1. Sliding Resistance 10-10
Equation 10.2. Ultimate Compression Capacity of a Single Pile 10-14
Equation 10.3. Ultimate Tension Capacity of a Single Pile 10-15
Equation 10.4. Load Application Distance for an Unbraced Pile 10-19
Equation 10.5. Determination of Square Footing Size for Gravity Loads 10-40
Equation 10.6. Determination of Soil Pressure 10-43

Chapter 13

Equation 13.1. Pile Driving Resistance for Drop Hammer Pile Drivers 13-8

List of Examples

Chapter 8

Example 8.1. Design Stillwater Flood Depth Calculations 8-11
Example 8.2. Wave Slam Calculation 8-27
Example 8.3. Hydrodynamic Load on Piles versus Breaking Wave Load on Piles 8-30

Example 8.4. Flood Load Example Problem 8-38
Example 8.5. Roof Uplift Connector Loads 8-54
Example 8.6. Lateral Diaphragm Loads from Wind Perpendicular to Ridge 8-57
Example 8.7. Roof Sheathing Suction Loads 8-64
Example 8.8. Lateral Connection Framing Loads from Wind 8-66
Example 8.9. Seismic Load 8-70
Example 8.10. Load Combination Example Problem 8-75

Chapter 9

Example 9.1. Roof Sheathing Nail Spacing for Wind Uplift 9-6
Example 9.2. Roof-to-Wall Connection for Uplift 9-9
Example 9.3. Uplift and Lateral Load Path at Window Header 9-14
Example 9.4. Uplift and Lateral Load Path at Wall-to-Floor Framing 9-15
Example 9.5. Uplift Load Path at Floor to Support Beam Framing 9-18
Example 9.6. Uplift Load Path for Support Beam-to-Pile 9-19
Example 9.7. Uplift and Compression Due to Shear Wall Overturning 9-21

Chapter 10

Example 10.1. Calculation for Allowable Capacities of Wood Piles 10-16
Example 10.2. Diagonal Brace Force 10-29
Example 10.3. Pier Footing Under Gravity Load 10-40
Example 10.4. Pier Footing Under Uplift Load 10-42
Example 10.5. Pier Footing Under Uplift and Lateral Loads 10-44

List of Worksheets

Chapter 8

Worksheet 1. Flood Load Computation Non-Tsunami Coastal A Zones (Solid Foundation) 8-44

Worksheet 2. Flood Load Computation Non-Tsunamic Zone V and Coastal A Zone (Open Foundation) 8-46

Worksheet 3. Load Combination Computation 8-80